

PREFLIGHT

Preflight Inspection	Completed
Seat Belts	Fastened
Doors	Closed
Fuel	Checked
Fuel Valve	Open
Flight Controls	Checked
Flaps	Up
Trim	Neutral

BEFORE START

Park Brake	On
Throttle	Closed
Master Switch	On
Code key	Use
Fuel Pump	On/Check/Off
Magnetos	Both On
Choke (when applicable)	On
Start Switch	Push
Choke (when applicable)	Off
Anti Collision Light	On

AFTER START

COM / TRANSPONDER	On
EFIS	On
Instruments	Checked & Set

TAXI

Brakes	Checked
--------	---------

BEFORE TAKEOFF

Park Brake	On
Engine Instruments	Checked (50C)
Fuel Valve	Open
Fuel pump	On
Choke	Off
Throttle	3000 RPM
Magnetos	Check
(Max: 200RPM / Diff: 50RPM)	
Throttle Idle	Check
Flaps	Flaps 15

AFTER TAKEOFF (>200 ft)

Flaps	Up
Fuel Pump (if applicable)	Off

DESCENT & APPROACH

Instruments	Checked & Set
Fuel	Checked
Fuel Pump	On
Magnetos	Both On
Seat Belts	Fastened

DOWNWIND

Fuel	Checked
Fuel Pump	On
Flaps	Flaps 1

FINAL

Flaps	Flaps 2
-------	---------

AFTER LANDING

Flaps	Up
Trim	Neutral

PARKING

Park Brake	On
Throttle	Idle
COM/TRANSP.	Off
EFIS Switch	Off
Fuel Pump	Off
Magnetos	Off
Master Switch	Off
Anti Coll. Light	Off
Fuel Valve	Closed